



# KINGS COUNTY COMMUNITY DEVELOPMENT AGENCY

Gregory R. Gatzka, Director

## BUILDING DIVISION

Darren Verdegaal, Deputy Director - Building Official

Web Site: [www.countyofkings.com](http://www.countyofkings.com)

### Submittal Requirements Solar Photovoltaic Installations 10 kW or Less One-Family and Two-Family Dwellings

This information is to help guide applicants through a streamlined permitting process for solar photovoltaic (PV) projects 10 kW in size or smaller. The following is information about submittal requirements for plan review, required fees and inspections.

#### 1. Approval Requirements

A building permit is required to install a solar PV system with a maximum power output of 10 kW or less. However, Planning and Fire Department review are not required for solar PV installations of this size.

#### 2. Submittal Requirements

- a) Completed permit application form. This permit application form can be downloaded at [www.countyofkings.com/departments/community-development-agency](http://www.countyofkings.com/departments/community-development-agency)
- b) Demonstrate compliance with the eligibility checklist for expedited permitting. These criteria can be downloaded at [www.countyofkings.com/departments/community-development-agency](http://www.countyofkings.com/departments/community-development-agency)
- c) A completed Standard Electrical Plan. The standard plan may be used for proposed solar installations 10 kW in size or smaller and can be downloaded at [www.countyofkings.com/departments/community-development-agency](http://www.countyofkings.com/departments/community-development-agency).
- d) A roof plan showing roof layout, PV panels and the following fire safety items: approximate location of roof access point, location of code-compliant access pathways, PV system fire classification and the locations of all required labels and markings. Examples of clear path access pathways are available in the State Fire Marshal Solar PV Installation Guide. <http://osfm.fire.ca.gov/pdf/reports/solarphotovoltaicguideline.pdf>.
- e) Completed expedited Structural Criteria along with required documentation. Structural Criteria can be downloaded at [www.countyofkings.com/departments/community-development-agency](http://www.countyofkings.com/departments/community-development-agency). For non-qualifying systems, provide structural drawings and calculations stamped and signed by a California-licensed civil or structural engineer, along with the following information:
  - The type of roof covering and the number of roof coverings installed
  - Type of roof framing, size of members and spacing
  - Weight of panels, support locations and method of attachment
  - Framing plan and details for any work necessary to strengthen the existing roof structure

- Site-specific structural calculations
- Where an approved racking system is used, provide documentation showing manufacturer of the rack system, maximum allowable weight the system can support, attachment method to the roof or ground and product evaluation information or structural design for the rack system

### **3. Plan Review**

Permit applications can be submitted to the Community Development Agency, Building Division, at 1400 W. Lacey Blvd. (Building #6), Hanford, CA or electronically to [kcbuilding@co.kings.ca.us](mailto:kcbuilding@co.kings.ca.us)

Permit applications utilizing standard plan may be approved “over-the-counter” at the Community Development Agency, Building Division, 1400 W. Lacey Blvd. (Building #6), Hanford, CA. Permit applications may also be submitted electronically for “over-the-counter” approval to [kcbuilding@co.kings.ca.us](mailto:kcbuilding@co.kings.ca.us)

Permits not approved “over-the-counter” should be reviewed in 5 business days.

### **4. Fees**

Per the latest approved fee schedule.

### **5. Inspections**

Once all permits to construct the solar installation have been issued and the system has been installed, it must be inspected before final approval is granted for the solar system. On-site inspections can be scheduled by contacting the Building Division by telephone at (559) 852-2672 or (559) 852-2652 or electronically at [www.countyofkings.com/departments/community-development-agency](http://www.countyofkings.com/departments/community-development-agency). Inspection requests received within business hours are typically scheduled for the next business day. If next business day is not available, inspection should happen within a five-day window.

Permit holders must be prepared to show conformance with all technical requirements in the field at the time of inspection. The inspector will verify that the installation is in conformance with applicable code requirements and with the approved plans.

The inspection checklist provides an overview of common points of inspection that the applicant should be prepared to show compliance. If not available, common checks include the following.

- Number of PV modules and model number match plans and specification sheets number match plans and specification sheets.
- Array conductors and components are installed in a neat and workman-like manner.
- PV array is properly grounded.
- Electrical boxes are accessible and connections are suitable for environment.
- Array is fastened and sealed according to attachment detail.
- Conductor’s ratings and sizes match plans.
- Appropriate signs are properly constructed, installed and displayed, including the following:
  - Sign identifying PV power source system attributes at DC disconnect
  - Sign identifying AC point of connection

- Sign identifying switch for alternative power system
- Equipment ratings are consistent with application and installed signs on the installation, including the following:
  - Inverter has a rating as high as max voltage on PV power source sign.
  - DC-side overcurrent circuit protection devices (OCPDs) are DC rated at least as high as max voltage on sign.
  - Switches and OCPDs are installed according to the manufacturer's specifications (i.e., many 600VDC switches require passing through the switch poles twice in a specific way).
  - Inverter is rated for the site AC voltage supplied and shown on the AC point of connection sign.
  - OCPD connected to the AC output of the inverter is rated at least 125% of maximum current on sign and is no larger than the maximum OCPD on the inverter listing label.
  - Sum of the main OCPD and the inverter OCPD is rated for not more than 120% of the bus bar rating.

## **6. Departmental Contact Information**

For additional information regarding this permit process, please consult our department website at [www.countyofkings.com/departments/community-development-agency](http://www.countyofkings.com/departments/community-development-agency) or contact Sydney Highfill at (559) 852-2672 or Toni Leist at (559) 852-2652.